

PLUMBING SCHEDULE	
SK1	MODULAR CABINETS WITH SINKS WILL BE INSTALLED BY TENANT - (UNDER SEPARATE CONTRACT). IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INSTALL THE TENANT PROVIDED SINK AND MODULAR SINKS. FAUCET TO MAKE A COMPLETE WORKING SYSTEM.
SK2	DOUBLE SINK, 3 HOLE, SELF RIM, 33"x19"x10"D, ELKAY #ELR331910, 1 1/2" 17GA P-TRAP W/C.O., #Z5920-ADM-1-GC BATTERY-POWERED SENSOR-OPERATED GOOSENECK FAUCET W/ 1.5GPM LAM. FLOW, LK-35 DRAIN, 3/8" FLEX RISERS &
SK3	MODULAR CABINETS WITH SINKS WILL BE INSTALLED BY TENANT - (UNDER SEPARATE CONTRACT). IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INSTALL THE TENANT PROVIDED SINK AND MODULAR SINKS. FAUCET TO MAKE A COMPLETE WORKING SYSTEM.
LAV	LAVATORY, WALL MOUNT, 21"x22", WHITE, KOHLER #K-2005, J.R. SMITH #700Z CARRIER, 1 1/4" 17GA P-TRAP W/C.O., SLOAN OPTIMA EAF-150-ISM BATTERY-POWERED SENSOR-OPERATED FAUCET W/ .55GPM SPRAY NOZZLE, ACQUIRE 155WC OFFSET DRAIN, ADA W/ RIM HEIGHT OF 34" A.F.F., 3/8" FLEX RISERS & L.K. STOPS, 1.5"W, 1.5"V, .5"CW, .5"HW.
WC	WATER CLOSET, FLOOR MT. REAR DISCH., HANDICAP, FLUSH VALVE (128GPF), ELONGATED BOWL, WHITE, AMERICAN STANDARD PROLO 1.1 - 1.6 GPF EVERCLEAN UNIVERSAL FLUSHMETER TOILET SENSOR-OPERATED FLUSH VALVE, NON-SLAM SEAT MT TOP OF FLUSH VALVE 30" A.F.F., CENTER OF WC 18" FROM SIDE WALL, 4"W, 2"V, 1"CW.

PLUMBING LEGEND:

SK1 SINGLE SINK
SK2 DOUBLE SINK
SK3 DEEP SINGLE
LAV WALL HUNG
WC - FLR. MTD RDISH

